


| Poz. | Zbrojenie   | Kształt | Stal  |
|------|-------------|---------|-------|
| 1    | 2φ12 l=5.01 | 5.01    | A-III |
| 2    | 5φ12 l=5.25 | 4.98    | A-III |
| 3    | 4φ6 l=1.18  | 0.29    | A-0   |
| 4    | 6φ6 l=0.70  | 0.09    | A-0   |

### Wykaz elementów

### Zestawienie stali

| Nr Stal     | Długość | Ilość | A0 φ6   | AIII φ12 |
|-------------|---------|-------|---------|----------|
| 1 12        | 5.01    | 2     |         | 10.02    |
| 2 12        | 5.25    | 5     |         | 26.25    |
| 3 6         | 1.18    | 49    | 57.82   |          |
| 4 6         | 0.70    | 6     | 4.20    |          |
| Razem       |         |       | 62.02   | 36.27    |
| Waga 1mb/kg |         |       | 0.222   | 0.888    |
| Razem       |         |       | 14.45   | 33.81    |
| OGÓŁEM      |         |       | 14.45kg | 33.81 kg |

### NADPROŻE POZ. 9.6



|  |   |                    |        |         |
|--|---|--------------------|--------|---------|
| <b>COMPLEX-PROJEKT</b><br>I Wzrzesniowska H Marchkowska<br>64-000 KOŚCIAN UL. MARCINIAKA 7 tel. 65 5123653 cproj@op.pl |   |                    |        |         |
| Obiekt   | Hala sportowa   |                    |        |         |
| Lokalizacja  | Gmina Pępowo  |                    |        |         |
| Inwestor   | Pępowo ul. Powstańców Wlkp.                           |                    |        | Nr rys. |
| Temat/Skala  | Projekt budowlany                                     |                    |        |         |
| Projektant   | mgr inż.<br>Leszek szymonowski<br>Nr upr 838 I 329/69 | Data<br>01-06-2009 | Podpis |         |
| Asystent   | tech arch<br>Sebastiaan Kaczmarek                     | Data<br>01-06-2009 | Podpis |         |

Stal A0,AIII 34GS  
Beton B-20 MPa